



HCNP-DCF-Build Facility Development Optimization

Huawei H12-425

Version Demo

Total Demo Questions: 15

Total Premium Questions: 240

Buy Premium PDF

<https://dumpsboss.com>

support@dumpsboss.com

dumpsboss.com

QUESTION NO: 1

Before installation, what is inside refrigerant pipe of the NetCol5000-A?

- A. Air
- B. Oxygen
- C. Nitrogen
- D. Refrigerant

ANSWER: C

QUESTION NO: 2

The straight pipe interval fixedly supported by NetCol5000-C piping is ()

- A. 3200mm
- B. 3000mm
- C. 2800mm
- D. 2500mm

ANSWER: D

QUESTION NO: 3

What should be done if the humidifier cylinder needs to be removed and maintained?

- A. Disconnect the cables of the water supply valve and the water drain valve.
- B. Remove the components of the water drain trough and valve
- C. Remove and clean the water supply valve.
- D. Replace the hose that has become rigid and fragile and thoroughly clean

ANSWER: A B C D

QUESTION NO: 4

The rack environment unit collects the environment data of IT cabinets

- A. TRUE
- B. FALSE

ANSWER: A**Explanation:**

EIM03C Rack Environment Unit User Manual <https://support.huawei.com/enterprise/en/doc/EDOC1000104402>

QUESTION NO: 5

FusionModule1000A series solution meets the TIER 4 requirements if it adopts 2N power supply and distribution system.

- A. TRUE
- B. FALSE

ANSWER: B**Explanation:**

(FM1000A does not support Tier 4)

QUESTION NO: 6

The work modes of rotary wheel free cooling solution are ().

- A. Compressor cooling mode
- B. Direct ventilation mode
- C. Mixed mode
- D. Free cooling mode

ANSWER: A C D

QUESTION NO: 7

The input line voltage of UPS5000-E supports ().

- A. 220V
- B. 380V
- C. 400V
- D. 415V

ANSWER: B C D

QUESTION NO: 8

Which type of report can be exported on the NetEco.

- A. Hourly report
- B. Daily report
- C. Weekly report
- D. Monthly report

ANSWER: A B C D

QUESTION NO: 9

Which statement are correct about UPS5000-E.

- A. It is modular UPS
- B. The input voltage range is 138-485V
- C. The input frequency range is 40-70Hz.
- D. A maximum of two UPS can be connected in parallel

ANSWER: A B C

QUESTION NO: 10

The power indicator of the gas fire extinguishing controller is on and the alarm indicator is off indicating that the gas fire extinguishing controller is working properly.

- A. TRUE
- B. FALSE

ANSWER: A**QUESTION NO: 11**

One NetCol520 chilled water distribution unit can support a maximum of () NetCol5000-C

- A. 12
- B. 10
- C. 8
- D. 6

ANSWER: A**QUESTION NO: 12**

Modbus card, SNMP card, dry contact card and CAN bus card are all available for UPS2000-G

- A. TRUE
- B. FALSE

ANSWER: B**QUESTION NO: 13**

The alarm management functions of the ECC800 include ().

- A. Viewing historical alarms
- B. Filtering alarms

- C. Exporting alarms
- D. Setting alarm parameters

ANSWER: A B C D

QUESTION NO: 14

The UPS5000 anti-seismic kit is applicable to earthquake-prone ones. When earthquake occurs, it provide support for cabinets

- A. TRUE
- B. FALSE

ANSWER: A

QUESTION NO: 15

The compressor suction pressure of NetCol5000-A25kW is low. It is possible that ().

- A. The electric heater is burnt out
- B. The refrigerant is insufficient.
- C. There is water vapor in the pipe
- D. The condensing pressure is low.

ANSWER: B D